
MINNESOTA DEPARTMENT OF TRANSPORTATION

GARRISON CONCOURSE OVERLOOK SITE RESTORATION AND ADA IMPROVEMENTS CONSTRUCTION PLAN FOR LOCATED ON T.H. 169 AT T.H. 18



DATE	SHEET NO.	APPROVED BY
UATE	SHEET NO.	ATTAVED BI
- 1		

DESIGN DESIGNATION - TIER NO.

PROJECT LOCATION COUNTY : CROW WING DISTRICT: 3

FOR PLANS & UTILITIES SYMBOLS SEE TECHNICAL MANUAL CHAPGE IDENTIFIER PROJ. NO 1804-87

TRANSPORTATION BUILDING

ST. PAUL, MINNESOTA 55155-1899

GARRISON CONCOURSE OVERLOOK - CITY OF GARRISON TITLE SHEET STATE PROJECT 1804-87 (TH169=018) SHEET NO. 1 OF 24 SHEETS

PRINT NAME

DATE

FED. PROJ. NO. STPX 1813(097)

TITLE SHEET

(SWPPP)

DELETED

PROTECTION PLAN

INLET PROTECTION

REMOVALS PLAN

LAYOUT PLAN ISLAND LAYOUT PLAN

GRADING PLAN CONSTRUCTION PLAN

PLANTING PLAN

SITE DETAILS

ADA DETAILS

PLANTING DETAILS

GOVERNING SPECIFICATIONS
THE 2005 EDITION OF THE MINNESOTA DEPARTMENT OF TRANSPORTATION
"STANDARD SPECIFICATIONS FOR CONSTRUCTION" SHALL GOVERN.

INDEX

STORM WATER POLLUTION PREVENTION PLAN

PROTECTION AND RESTORATION OF VEGETATION TEMPORARY SEDIMENT CONTROL - STORM DRAIN

TEMPORARY SEDIMENT CONTROL - SILT FENCE

WALL, STONE PAVER, AND BENCH DETAILS

THIS PLAN CONTAINS 24 SHEETS

THE STATE OF MINNESOTA.

43014

STATEMENT OF ESTIMATED QUANTITIES

EXISTING CONDITIONS AND SITE

VISITOR CENTER LAYOUT PLAN

SUBSURFACE DRAINAGE PLAN

SHEET 12 HAS BEEN DELETED

SUBSURFACE DRAINAGE DETAILS

DATE MODIFIED: DRAWN BY: TAG

AUGUST 21, 2012 CHECKED BY: TAG FILE SERVER LOCATION: M:\Projects\Garrison Concourse\Construction Documents\Garrison.dwg

HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA.

PRINTED NAME: TODD GROVER

DATE: AUGUST 21, 2012 LIC. NO. 43014



STATE OF MINNESOTA
DEPARTMENT OF TRANSPORTATION

LIC.NO.

MADE BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY

SIGNATURE

I HEREBY CERTIFY THAT THE FINAL FIELD REVISIONS IF ANY OF THIS PLAN WERE LICENSED DESIGN PROFESSIONAL UNDER THE LAWS OF THE STATE OF MINNESOTA.

STATEMENT OF ESTIMATED QUANTITIES

item Number	ПЕМ	NOTE NUMBER	UNIT	TOTAL ESTIMATED QUANTITY	
2021.501	MOBILIZATION		LUMP SUM	1	
2101.511	CLEARING AND GRUBBING		LUMP SUM	1	
		<u> </u>			
2104.501	REMOVE CONCRETE CURB (P)		LIN FT	292	
2104.503	REMOVE CONCRETE WALK (P)	(1)	SQ FT	666	
2104.505	REMOVE CONCRETE WALK (P)	(2)	SQ YD	536	
2104.505	REMOVE BITUMINOUS PAVEMENT (P)		SQ YD	3454	
2104.513	SAWING BIT PAVEMENT (FULL DEPTH)	ļ <u>. </u>	LIN FT	98	
2104.521	SALVAGE STONE CURB	(3)	LIN FT	1285	
2104.523	SALVAGE CASTING		EACH	4	
2104.525	ABANDON CATCH BASIN	/=\	EACH	2	
2104.602	RELOCATE BENCH	(5)	EACH	2	
2104.618	SALVAGE STONE PAVERS	(3)	SQ FT	6000	
2104.618	REMOVE STONE	(6)	SQ FT	20	
0405.504	COLUMNIA EVOLUTION		011.10	7507	
2105.501	COMMON EXCAVATION	ļ <u>,_</u> ,	CU YD	3587	
2105.525	TOPSOIL BORROW (LV)	(7)	CU YD	177	
2105.526	SELECT TOPSOIL BORROW (LV)	(7)	CU YD	128	
2105.604	GEOTEXTILE FILTER TYPE V		SQ YD	539	
		ļ <u> </u>			
2211.503	AGGREGATE BASE (CV) CLASS 5	(8)	CU YD	576	
2211.503	AGGREGATE BASE (CV) CLASS 2 MOD	(9)	CU YD	245	
		4 >	ļ		
2301.531	EXPANSION JOINTS DESIGN SPECIAL	(10)	LIN FT	400	
		1,			
2360.503	TYPE SP 12.5 WEAR CRS MIX (2,C) 2.0" THICK	(11)	SQ YD	6908	
	COLDER ELIZED LOOPEOLYTE (O.)	<u> </u>	011.1/0	45	
2451.511	COARSE FILTER AGGREGATE (CV)	(10)	CU YD	45	
2451.513	FINE FILTER AGGREGATE (LV)	(12)	CU YD	643	
2522 524	C" DVO SIDE DDAN	// 23	1111 575	750	
2502.521	6" PVC PIPE DRAIN	(13)	LIN FT	359	
2502.541	4" PERF PVC PIPE DRAIN	(13)	LIN FT	367	
2502.602	4" PVC PIPE DRAIN CLEANOUT	(14)	EACH	6	
0500 501	INICTALL CACTARO		FACU	1	
2506.521	INSTALL CASTING	(4.5)	EACH	4	
2506.522	ADJUST FRAME AND RING CASTING	(15)	EACH	2	
2506.602	CONNECT INTO EXISTING DRAINAGE STRUCTURE		EACH	4	
2524 524	o" complete walk	-		710	
2521.501	6" CONCRETE WALK	-	SQ FT	719	
2571 501	CONCRETE CURE AND CUTTER DESIGN RESA	ļ	1 IN CT	292	
2531.501	CONCRETE CURB AND GUTTER DESIGN B624	ļ	LIN FT	84	
2531.603	CONCRETE CURB DESIGN V		LIN FT	26	
2531.618	TRUNCATED DOMES		SQ FT	20	
	BELOOJE WOOD STOUGHE	7.1	7.011	_	
2540.602	RELOCATE MISCELLANEOUS STRUCTURE	(4)	EACH	2	
2540.602	BENCH	(18)	EACH	6	
2540.603	LANDSCAPE EDGER	(19)	LIN FT	1880	
		(0.0)	1	1.000	
2541.603	RESTORE HISTORIC CURB	(20)	LIN FT	1286	
2541.618	INSTALL STONE	(21)	SQ FT	20	
2541.618	REPOINT HISTORIC STRUCTURE	(22)	SQ FT	800	
2541.618	CLEAN HISTORIC STRUCTURE	(23)	SQ FT	800	
2541.618	RESTORE HISTORIC PAVERS	(24)	SQ FT	4848	
			11110 01111	4	
2563.601	TRAFFIC CONTROL		LUMP SUM	1	
2571.502	DECIDUOUS TREE 2.5" CAL B&B		TREE	8	
2571.505	DECIDUOUS SHRUB NO 5 CONT	ļ	SHRUB	204	
2571.602	TREE PROTECTION		EACH	12	
				1.50	
2573.502	SILT FENCE, TYPE HEAVY DUTY		LIN FT	150	
2573.530	STORM DRAIN INLET PROTECTION		EACH	6	
				ļ	
2575.505	SODDING TYPE SALT RESISTANT	(25)	SQ YD	784	
2575.521	EROSION CONTROL NETTING	(26)	SQ YD	336	
2575.550	COMPOST GRADE 2	(27)	CU YD	107	

STATEMENT OF ESTIMATED QUANTITIES NOTES:

- INCLUDES THE EXISTING CONCRETE WALKS AT THE FIBERGLASS WALLEYE MONUMENT, THE WALK TO THE STONE MONUMENT, AND THE WALK TO THE VISITORS INFORMATION BOOTH.
- INCLUDES THE WALK, CURB AT DRIVE, AND THE CURB AT THE WALL AT THE OVERLOOK WALL THAT WAS PLACED OVER EXISTING STONE PAVERS AND CURB. EXISTING PAVERS AND CURB REMAIN UNDER THE CONCRETE WALK. REMOVAL OF THE CONCRETE WALK AND CURBS MUST BE DONE IN A MANNER THAT WILL NOT DAMAGE THE UNDERLYING PAVERS, CURB, AND ADJACENT HISTORIC WALL.
- INCLUDES EXISTING, HISTORIC MATERIALS ON-SITE THAT ARE IN GOOD CONDITION AS DETERMINED BY THE HISTORIC ARCHITECT AS INDICATED ON THE DRAWINGS OR IN THE FIELD PRIOR TO COMMENCEMENT. MATERIALS WILL BE DISMANTLED WITHOUT DAMAGE AND STORED FOR REINSTALLATION DURING RESTORATION WORK, DOCUMENT THE LOCATION OF EACH STONE PRIOR TO DISMANTLING WHERE RESTORATION WORK REQUIRES THE STONE BE PLACED IN THE SAME LOCATION.
- THE FIRST MONUMENT TO BE RELOCATED IS THE FIBERGLASS WALLEYE FISH AND BASE. THE WORK WILL ENTAIL THE REMOVAL OF THE MONUMENT FROM ITS EXISTING LOCATION AND THE MOVING OF THE MONUMENT, WITHOUT DAMAGE, TO THE NEW LOCATION, SEE SHEET 11. THE MONUMENT IS CURRENTLY ATTACHED TO THE CONCRETE PAD AT THE BASE WITH ANCHOR BOLTS AND THIS SAME CONNECTION METHOD WILL BE USED AT THE NEW LOCATION. THE SECOND MONUMENT TO BE RELOCATED IS THE TAUER MONUMENT. THE WORK WILL ENTAIL THE EXCAVATION AND REMOVAL OF THE MONUMENT FROM ITS EXISTING LOCATION AND MOVING THE MONUMENT, WITHOUT DAMAGE, TO THE NEW LOCATION ON SHEET 11. THE MONUMENT WILL BE PLACED IN THE SAME MANNER AS CURRENTLY EXISTS.
- RELOCATE EXISTING BENCHES ON SITE. INCLUDES THE CONCRETE BENCH SEATS AND STONE SUPPORTS. STONE SUPPORTS TO BE LABELED, DISMANTLED, CLEANED AND REBUILT IN NEW LOCATION.
- INCLUDES EXISTING, HISTORIC MATERIALS ON-SITE THAT ARE DETERIORATED AND CANNOT BE REUSED AS DETERMINED BY THE HISTORIC ARCHITECT AS INDICATED ON THE DRAWINGS OR IN THE FIELD PRIOR TO COMMENCEMENT. MATERIALS WILL BE DISMANTLED AND DISPOSED.
- TOPSOIL BORROW (LV) TO BE USED FOR SOD INSTALLATION. SELECT TOPSOIL BORROW (LV) TO BE USED FOR PLANT INSTALLATION.
- FOR PLACEMENT UNDER BITUMINOUS PAVEMENT, STONE PAVERS, CURBING AND CONCRETE WALK
- FOR STABILIZED AGGREGATE WALKS ON ISLAND. 100% CRUSHED GRANITE MIX WITH PORTLAND CEMENT (INCIDENTAL) PER DETAIL 1/21.
- FURNISH AND INSTALL AT PAVER/WALL AND WALL/PIER INTERSECTION. SEE DETAILS 2/24 AND 5/24.
 - TACK COAT IS INCIDENTAL.
- QUANTITY INCLUDES THAT REQUIRED FOR DRAINAGE BED AND FOR MIXING WITH COMPOST FOR DRAINAGE MEDIUM AND PLANTING MEDIUM.
- INCLUDES WYES, EXTRA PIPE, ALL CONNECTIONS AND COUPLINGS, AND GEOTEXTILE FABRIC TYPE I (INCIDENTAL).
- FURNISH AND INSTALL SOLID CAP AT GRADE (INCIDENTAL).
- TO BE ADJUSTED TO NEW DRIVE ELEVATION.
- THESE PEDESTRIAN RAMPS USE HISTORIC/SALVAGED AND NEW PAVERS FOR THE FLARE PORTIONS OF THE RAMP. SEE DETAIL 1/22.
- THESE PEDESTRIAN ACCESS POINTS USE A CONCRETE STRAIGHT RUN WITH INTEGRATED CONCRETE CURB AT TURF EDGE. HISTORIC STONE CURB IS PLACED BETWEEN THE TURF/CONCRETE AND THE BITUMINOUS DRIVE. SEE DETAILS 2/22 AND 1/23.
- BENCH MUST MATCH EXISTING BENCH IN STYLE AND CONSTRUCTION. EXISTING BENCH IS A PRE-CAST CONCRETE SEAT WITH TWO STONE SUPPORTS STONE SUPPORTS ARE CUT AND SHAPED GRANITE TO MATCH EXISTING. BENCHES INCLUDE 4 STRAIGHT SEAT BENCHES AND 2 CURVED SEAT BENCHES, SEE DETAILS 6/24.
- STEEL EDGER. SUBMIT FOR APPROVAL. SEE DETAILS SHEET 21.
- INCLUDES THE REBUILDING OF STONE CONSTRUCTION USING SALVAGED STONE FROM PREVIOUS OPERATIONS. PLACE STONE IN THE SAME LOCATION AS
- DOCUMENTED PRIOR TO DISMANTLING. SEE SHEET 24.
 INCLUDES NEW MATERIAL AND LABOR NECESSARY TO INSTALL STONE AT AREAS WHERE DETERIORATED STONE WAS REMOVED OR STONE WAS MISSING. INSTALIATION INCLUDED THE SELECTING, SHAPING, AND PLACEMENT OF STONE TO REPLICATE CHARACTER OF HISTORIC STONE WHERE STONE WAS REMOVED OR CHARACTER OF ADJACENT STONE CONSTRUCTION WHERE STONE WAS MISSING.
- REPOINT WALL 100% AT THE BASE OF THE WALL WHERE THE CONCRETE WALKWAY WAS REMOVED TO 1 FOOT BELOW HISTORIC PAVER LEVEL. THE EXCAVATION OF 1' TO FACILITATE REPOINTING IS INCIDENTAL. SEE SHEET 24 FOR DETAILS.
- AFTER THE CONCRETE WALK IS REMOVED, CLEAN LOWER WALL OF CEMENT STAINS PRIOR TO RESTORING AND REPOINTING STONE.
- INCLUDES THE REBUILDING OF STONE PAVER CONSTRUCTION USING SALVAGED STONE FROM PREVIOUS OPERATIONS. PLACE STONE IN THE SAME LOCATION AS DOCUMENTED PRIOR TO DISMANTLING. SEE SHEET 15 FOR GRADING AND SLOPES.
- PER MNDOT 3878. SOD BED PREPARATION AND 45 DAY MAINTENANCE PERIOD ARE INCIDENTAL.
- TYPE I. FURNISH AND INSTALL WITHIN 3' OF BOTH SIDES OF AGGREGATE WALKS UNDER SOD.
- FOR MIXING WITH FINE FILTER AGGREGATE FOR DRAINAGE MEDIUM AND PLANTING MEDIUM.

GENERAL NOTES:

- THIS PROJECT WILL RESTORE THE HISTORIC CONCOURSE SITE MATCHING ORIGINAL DESIGN AND MATERIALS AS SHOWN IN THE PLAN. THE PROJECT WILL ALSO RELOCATE EXISTING SITE ELEMENTS (FIBERGLASS WALLEYE MONUMENT, THE TAUER MONUMENT, AND VISITORS INFORMATION BOOTH).
- ALL WORK AND MATERIALS MUST BE IN ACCORDANCE WITH THE SECRETARY OF INTERIOR'S STANDARDS AND WILL BE STRICTLY ENFORCED. ANY WORK IN ADDITION MUST BE APPROVED IN ADVANCE OF WORK
- STONE PAVER REPLACEMENT SHALL BE OF THE SAME SIZE, COLOR, TEXTURE, FINISH, PATTERN, AND APPEARANCE OF HISTORIC STONE SHOWN ON IMAGES OR EXISTING ON SITE.
- USE BEST MANAGEMENT PRACTICES TO PROTECT WATER QUALITY. FOR EXAMPLE, CONTROL THE SPREAD OF DUST AND MORTAR MATERIAL AND AVOID ALLOWING ANY MORTAR MATERIAL OR WASTE TO ENTER "WATERS OF THE STATE" (INCLUDES CATCH BASINS, DITCHES, ETC). ALL MORTAR WASTE SHALL BE REMOVED FROM THE PROJECT AND DISPOSED PER MNDOT 1717.
- CONTRACTOR IS RESPONSIBLE FOR CONFIRMATION OF MATERIAL QUANTITIES REQUIRED.
- REMOVE AND DISPOSE OF ALL DEBRIS PER MNDOT 1717.
- ALL DIMENSIONS AND SLOPES ARE AS SHOWN ON TYPICAL SECTIONS EXCEPT AS SHOWN ELSEWHERE ON THE PLAN.
- PROPERTY TO DRAIN TO DISCHARGE POINTS.

GARRISON CONCOURSE PUBLIC UTILITIES

MILLE LACS ENERGY COOPERATIVE	RELOCATE OVERHEAD POWER
FRONTIER COMMUNICATIONS OF MINNESOTA	RELOCATE SERVICE LINE
MINNESOTA DEPARTMENT OF TRANSPORTATION	NO IMPACT

UTILITY NOTES:

- OVERHEAD ELECTRICAL LINES WILL BE RELOCATED WITH BURIED POWER BY OTHERS.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO UTILIZE THE "GOPHER ONE CALL EXCAVATION NOTICE" (1-800-252-1166) REQUIRED BY MINNESOTA
- THE SUBSURFACE UTILITY INFORMATION IN THIS PLAN IS UTILITY LEVEL QUALITY D. THE UTILITY LEVEL WAS DETERMINED ACCORDING TO THE GUIDELINES OF CI/ASCE 38-02 ENTITLED "STANDARD GUIDELINES FOR THE COLLECTION AND DÉPICTION OF EXISTING SUBSURFACE"

STANDARD PLATES

NOTE: THE FOLLOWING STANDARD PLATES APPROVED BY THE DEPARTMENT OF TRANSPORTATION, FEDERAL HIGHWAY ADMINISTRATION, SHALL APPLY ON THIS

4026A	CONCRETE ENCASED CONCRETE ADJUSTING RINGS
4108F	ADJUSTING RINGS FOR CATCH BASINS AND MANHOLES
7038A	DETECTABLE WARNING SURFACE - DOMES ONLY
7100H	CONCRETE CURB AND GUTTER
80008	STANDARD BARRICADES

DATE MODIFIED: AUGUST 23, 2012

FILE SERVER LOCATION:

DRAWN BY: TAG CHECKED BY: TAG

M:\Projects\Garrison Concourse\Construction Documents\Garrison.dwg

HERERY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA

PRINTED NAME: TODD GROVER DATE: AUGUST 23, 2012 LIC. NO. 43014






STATE OF MINNESOTA DEPARTMENT OF TRANSPORTATION

TRANSPORTATION BUILDING ST. PAUL, MINNESOTA 55155-1899 GARRISON CONCOURSE OVERLOOK - CITY OF GARRISON STATEMENT OF ESTIMATED QUANTITIES AND STD PLATES

STATE PROJECT 1804-87 (TH169)

SHEET NO. 2 OF 24 SHEETS



GARRISON CONCOURSE SITE RESTORATION STORM WATER POLLUTION PREVENTION PLAN (SWPPP) TH169 IN GARRISON, CROW WING COUNTY. THIS PROJECT WILL RESTORE THE CONCOURSE SITE AND RENOVATE EXISTING ELEMENTS MATCHING ORIGINAL CONSTRUCTION AND MATERIALS DESIGNATED HISTORIC. THE INTENT IS

AREA DISTURBED IS 1.5 ACRES AND INCLUIDES THE DRIVE SIDE OF THE STONE WALL, THE DRIVE, ACCESS FROM TH169, ISLAND, DITCHES, STAGING AREAS, AND ACCESS TO SITE FROM THIESE, THERE WILL BE NO CHANGE IN IMPERVIOUS SURFACE.

THE FOLLOWING SPECIAL OR IMPAIRED WATERS ARE WITHIN 1 MILE OF THIS PROJECT: LAKE MILLE LACS - IMPAIRED FOR MERCURY.

THE ULTIMATE RECEIVING WATER IS LAKE MILLE LACS BY DIRECT DISCHARGE, GROUND WATER INFILTRATION, DITCHES, CURB AND GUTTER INLETS, AND CULVERTS THE POTENTIAL POLLUTANTS GENERATED FROM THIS WORK INCLUDE THE FOLLOWING: STONE DUSTS, MASONRY AND MORTAR DUSTS, PORTLAND CEMENT, HYDRATED LIME, MORTAR PIGMENTS, FUELS, SOLVENTS, CLEANING/DETERGENT AGENTS, SEDIMENTS, HOT WATER, AND OILS FROM BITUMINOUS.

PROJECT CONTACTS

MN/DOT RESIDENT ENGINEER (DISTRICT 3)	TONY HUGHES	218-828-5735
MN/DOT CONSTRUCTION PROJECT MANAGER (HISTORIC)	KATHRYN McFADDEN	651-366-4641
MN/DOT DNR LIAISON	PETER LEETE	651-366-3634
MN DNR - AREA HYDROLOGIST	JOE OSCHWALD	218-833-8687
USACE - CROW WING COUNTY PROJECT MANAGERS	LEO GRABOWSKI	651-290-5357
CROW WING COUNTY SOIL AND WATER CONSERVATION DISTRICT — WCA LGU	KEITH POHL	218-828-6197
CROW WING - PLANNING AND ZONING	BONNIE FINNERTY	218-824-1125
MPCA	SCOTT LUCAS	218-316-3874
MPCA – 24 HR EMERGENCY NOTIFICATION STATE DUTY OFFICER		651-649-5451 800-422-0798
Mn/DOT EROSION CONTROL	BRENT TROYER	651-366-3629
EROSION CONTROL SUPERVISOR	TBD	

BMP INSTALLATION, MAINTENANCE AND OPERATIONS:

THE ENTIRE PROJECT SHALL USE THE SITE PLAN PROCESS AS PER Mn/DOT 1717. ADDITIONAL SITE PLANS SHALL BE SUBMITTED WHEN REQUESTED BY THE PROJECT ENGINEER OR AS INDICATED IN THE PLAN. Mn/DOT 1717 SITE PLANS SHALL BE DEVELOPED BY THE CONTRACTOR PRIOR TO ANY WORK ADJACENT TO LAKE MILLE LACS, AND ALL STONE CUTTING, MORTAR GRINDING, AND STONE CLEANING OPERATIONS. IT IS EXPECTED THAT THE CONTRACTOR USE BEST MANAGEMENT PRACTICES TO PREVENT THE DISCHARGE OF FUGITIVE DUSTS BY USE OF WATER MISTS OR PLASTIC SHROUDS AND VACUUMS.

FINAL TURF RESTORATION SHALL BE AS PER PRE-EXISTING CONDITION, AS CERTIFIED SALT TOLERANT SOD OR EQUIVALENT.

THE CONTRACTOR SHALL DEVELOP A QUALITY ASSURANCE PROGRAM AS PER 1717, THE CONTRACTOR SHALL PERFORM DAILY INSPECTIONS AND CORRECT ANY EROSION AND SEDIMENT CONTROL DEFICIENCIES, INCLUDING THOSE DISCOVERED AFTER EVERY 0.5 INCH RAIN EVENT. THE INSPECTION REPORT SHALL BE IN WRITING ALONG WITH PHOTOGRAPHS, AND SUBMITTED TO THE PROJECT ENGINEER EVERY WEEK DURING SOIL DISTURBANCE OPERATIONS. ONCE THE SITE HAS BEEN STABILIZED, THE INSPECTIONS SHALL BE DONE EVERY 30 DAYS, OR UNTIL 70 PERCENT PERENNIAL VEGETATIVE COVER HAS BEEN ESTABLISHED OVER THE WHOLE SITE. THE CONTRACTOR IS REMINDED TO TERMINATE THE PERMIT COVERAGE WITHIN 30 DAYS OF MEETING THE NPDES REQUIREMENTS, IF APPLICABLE.

THE CONTRACTOR IS RESPONSIBLE TO MAINTAIN ALL BMPs THROUGHOUT THE PROJECT.

RECEIVING SURFACE WATERS AND ENVIRONMENTALLY SENSITIVE AREAS:

THE RECEIVING WATER FOR STORM WATER RUNOFF FROM THIS PROJECT IS MILLE LACS LAKE. MILLE LACS LAKE LISTED AS IMPAIRED ON THE MPCA'S CWA 303D UST OF IMPAIRED WATERS. THE IMPAIRMENT IS MERCURY.

MILLE LACS LAKE IS CONSIDERED DNR PROTECTED WATER. NO WORK SHALL OCCUR WITHIN MILLE LACS LAKE BETWEEN APRIL 15 AND JUNE 1 TO MINIMIZE IMPACTS ON FISH SPAWNING AND MIGRATION. THE DNR FISHERIES SUPERVISOR MAY BE CONTACTED ABOUT WAIVING WORK EXCLUSION DATES WHERE WORK IS ESSENTIAL OR WHERE IT CAN BE DEMONSTRATED THAT A PROJECT WILL MINIMIZE IMPACTS TO HABITAT AND SPAWNING.

INVASIVE SPECIES:

EURASIAN WATERMILFOIL. SPINY WATER FLEA, CURLY-LEAF PONDWEED, AND ZEBRA MUSSELS ARE PRESENT WITHIN MILLE LACS LAKE. IN ORDER TO PREVENT THE SPREAD OF INVASIVE SPECIES, ALL EQUIPMENT INTENDED FOR USE AT THE PROJECT MUST BE INSPECTED BY MN/DOT PRIOR TO USE AND MUST POSSESS DOCUMENTATION OF LAST USE AND THAT DOCUMENTATION PROTOCOLS WERE FOLLOWED.. FOLLOWING USE, ALL VISIBLE AQUATIC REMNANTS (PLANTS, SEEDS, MUD, SOIL, AND ANIMALS) MUST BE REMOVED FROM ALL EQUIPMENT THAT HAD BEEN IN CONTACT WITH THE LAKE. EQUIPMENT MUST BE TREATED AS FOLLOWS:

CLEAN BEFORE BEING TRANSPORTED FROM THE PROJECT SITE. POWER WASHING/SPRAYING. PREFERABLE WITH HOT WATER (FOLLOWED BY DRYING FOR 7 DAYS) IS AN ACCEPTABLE METHOD TO ENSURE KILLING AND REMOVING OF INVASIVE SPECIES.

DRAIN BEFORE TRANSPORTING FROM WORK SITE. DRAIN ALL WATER FROM EQUIPMENT WHERE WATER MAY BE TRAPPED SUCH AS TANKS, PUMPS, HOSES, SILT CURTAIN, AND WATER-RETAINING COMPONENTS OF BOATS/BARGES.

DRY AFTER SPRAYING AND DRAINING, DRY EQUIPMENT THAT HAS BEEN IN INFESTED WATERS FOR A MINIMUM OF 7 DAYS BEFORE RE-USE OR HAULING AWAY.

CONTACT PETER LEETE, DNR TRANSPORTATION HYDROLOGIST AT PETERLEETE@STATE.MN.US OR (651) 366-3634 IF THE CONDITIONS ABOVE ARE NOT ABLE TO BE MET.

RARE PLANT OR ANIMAL SPECIES:

BLANDINGS TURTLES, A STATE-LISTED ENDANGERED AND THREATENED SPECIES, HAVE BEEN REPORTED IN THE VICINITY OF THE PROJECT AND MAY BE ENCOUNTERED ON-SITE. IF BLANDINGS TURTLES ARE FOUND ON SITE, STATE LAW AND RULES PROHIBIT THE DESTRUCTION OF THREATENED OR ENDANGERED SPECIES, IF TURTLES ARE IN IMMINENT DANGER, THEY SHOULD BE MOVED BY HAND OUT OF HARM'S WAY, OTHERWISE THEY SHOULD BE LEFT UNDISTURBED. A BLANDINGS TURTLE FACT SHEET THAT DESCRIBES THE HABITAT USE AND LIFE HISTORY OF THIS SPECIES, INCLUDING A LIST OF RECOMMENDATIONS FOR AVOIDING AND MINIMIZING IMPACTS, IS PROVIDED IN SPECIAL PROVISIONS.

EROSION CONTROL SUPERVISOR

IN ACCORDANCE WITH SPEC. 2573.3 THE CONTRACTOR WILL PROVIDE A CERTIFIED EROSION CONTROL SUPERVISOR IN GOOD STANDING WHO IS KNOWLEDGEABLE AND EXPERIENCED IN THE APPLICATION OF EROSION PREVENTION AND SEDIMENT CONTROL BMPS. THE EROSION CONTROL SUPERVISOR IS INCIDENTAL. THE EROSION CONTROL SUPERVISOR WILL WORK WITH THE PROJECT ENGINEER TO OVERSEE THE IMPLEMENTATION OF THE SWPPP AND THE INSTALLATION, INSPECTION, AND MAINTENANCE OF THE EROSION PREVENTION AND SEDIMENT CONTROL BMPS BEFORE, DURING AND AFTER CONSTRUCTION UNTIL THE NOTICE OF TERMINATION (NOT) HAS BEEN FILED WITH THE MPCA

DATE MODIFIED: AUGUST 23, 2012 FILE SERVER LOCATION:

DRAWN BY: TAG CHECKED BY: TAG

M:\Projects\Garrison Concourse\Construction Documents\Garrison.dwg

HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA.

SIGNATURE: PRINTED NAME: TODD GROVER DATE: AUGUST 23, 2012 LIC. NO. 43014





STATE OF MINNESOTA DEPARTMENT OF TRANSPORTATION

TRANSPORTATION BUILDING ST. PAUL. MINNESOTA 55155-1899

GARRISON CONCOURSE OVERLOOK - CITY OF GARRISON STORM WATER POLLUTION PREVENTION PLAN (SWPPP)

SHEET NO. 4 OF 24 SHEETS STATE PROJECT 1804-87 (TH169)

EROSION CONTROL MEASURES:

TIMING OF BMP INSTALLATION:

THE CONTRACTOR IS RESPONSIBLE FOR MINIMIZING SOIL EROSION AND PREVENTING DAMAGE TO MILLE LACS LAKE FROM SEDIMENTATION OVER THE VARIOUS STAGES OF CONSTRUCTION AT ALL SEASONAL TIMES DURING THE YEAR FOR THE DURATION OF THE CONTRACT.

A SITE PLAN DETAILING PROPOSED EROSION CONTROL AND SEDIMENT CONTROL MEASURES AND A SCHEDULE INDICATING STARTING AND COMPLETION TIMES

FOR CONSTRUCTION OPERATIONS SHALL BY SUBMITTED TO MN/DOT BY THE CONTRACTOR IN ACCORDANCE WITH MN/DOT SPEC 1717.2E. THE CONTRACTOR

ALL DISTURBED, EXPOSED SOILS MUST BE STABILIZED IMMEDIATELY BY SEEDING AND MULCHING AND/OR RIPRAP WITH FILTER FABRIC IF THE SOILS ARE

THE CONTRACTOR SHALL PROVIDE APPROPRIATE EROSION CONTROL DEVICES FOR STOCKPILE AREAS (INCIDENTAL).

SHALL NOT START WORK UNTIL THE SCHEDULE AND SITE PLAN HAVE BEEN ACCEPTED BY MN/DOT.

NOT TO BE WORKED WITHIN 24 HOURS (INCLUDING WEEKENDS AND HOLIDAYS).

TURF, CONVEYANCE, AND LAKE BOTTOM OUTFALLS MUST BE PROTECTED FROM CEMENTITIOUS MATERIALS, SEDIMENTS, AND CHEMICAL CLEANING AGENTS BY AVOIDANCE, USE OF PLASTIC SHEETING, COMPOST FILTER LOGS OR OTHER PROJECT ENGINEER APPROVED METHODS. THE CONTRACTOR SHALL PREVENT DISCHARGE TO SURFACE AND GROUND WATERS BY VACUUM OR SWEEP COLLECTION OF ALL CEMENTITIOUS MATERIALS, CLEANING AGENTS FROM PLASTIC GROUND COVERS, MATS, OR OTHER PROJECT ENGINEER APPROVED METHOD.

ANY RUTS OR DAMAGED TURF THAT COULD CREATE SEDIMENT DISCHARGE TO LAKE MILLE LACS AND CONVEYANCE SYSTEMS MUST BE REPAIRED WITHIN 24 HOURS WITH SHAPING, SEEDING AND CERTIFIED WEED FREE STRAW MULCH MATERIALS. EFFORT MUST BE MADE TO PREVENT REOCCURRENCE OF SOIL DISTURBANCE BY PROTECTIVE SOIL COVERS

TEMPORARY SHORT TERM WORK GENERATING CONCRETE, MORTAR, OR STONE DEBRIS MAY USE GEOTEXTILE INLET FILTER STOPS, BUT MUST BE REPLACED WITH CURB AND GUTTER INLET SACKS WITH EMERGENCY OVERFLOW WILL BE USED, AS NEEDED, TO PROTECT INLETS AND LAKE MILLE LACS OVER THE LIFE OF THE CONTRACT WHEN EXPOSED SOILS WITH THE POTENTIAL TO DISCHARGE ARE UPGRADIENT TO THE INLET, OR DURING ACCESS AND TRACK-OUT OPERATIONS. PICKUP (ENCLOSED SKIDSTEER BROOM) SWEEPING OF ALL PAVED SURFACES WILL BE REQUIRED, AS NECESSARY TO KEEP SEDIMENTS, MUD, DIRT, ROCK, OR OTHER MATERIALS FROM LEAVING THE PAVED SURFACE DUE TO RAIN OR VEHICLE TRACKING.

CULVERT ENDS WILL BE PROTECTED FROM SEDIMENT DISCHARGE USING COMPOST FILTER LOGS, WOOD-FIBER LOGS, OR WOOD CHIP LOGS, AS NEEDED.

SLOPED GRADES MUST BE PROTECTED, ANY SOIL DISTURBED AREAS SHALL BE KEPT IN A PERPETUALLY STABILIZED CONDITION

SOFT SOIL CROSSING WILL REQUIRE DRIVABLE MATS CAPABLE OF MINIMIZING SOIL DISTURBANCE FOR THE CONTRACTORS' EQUIPMENT. THIS MAY BE ACCOMPLISHED BY USE OF PLYWOOD, MUD MATS, OR STRUCTURAL PLASTIC BASE UNITS.

ALL PERIMETER CONTROL BMPS SHALL BE KEPT IN A FUNCTIONAL CONDITION. REGARDLESS OF NUMBER OF MOVEMENTS TO ACCOMMODATE THE CONTRACTORS OPERATIONS, PERIMETER CONTROL SHALL BE IN THE FORM OF 3987 FILTER LOGS, TYPE COMPOST LOG.

ALL TRASH AND CONSTRUCTION DEBRIS SHALL BE PICKED UP AT THE END OF EACH DAY AND PLACED IN DUMPSTER OR OTHER SUITABLE CONTAINERS, AND REMOVED AS NECESSARY TO REMAIN FUNCTIONAL.

FERTILIZER SHALL BE PHOSPHOROUS FREE AND BE INCORPORATED INTO THE TILLING AND PREP OPERATION BEFORE SOD IS INSTALLED.

TEMPORARY SEDIMENT CONTROL MEASURES:

SEDIMENT CONTROL PRACTICES MUST MINIMIZE SEDIMENT ENTERING MILLE LACS LAKE, SEDIMENT CONTROL PRACTICES MUST BE ESTABLISHED ON ALL DOWN-GRADIENT PERIMETERS BEFORE ANY UP-GRADIENT LAND DISTURBING ACTIVITIES BEGIN. THESE PRACTICES SHALL REMAIN IN PLACE UNTIL FINAL STABILIZATION HAS BEEN ESTABLISHED.

THE CONTRACTOR SHALL USE A TEMPORARY ROCK CONSTRUCTION PAD OR OTHER APPROPRIATE BMPS AT MAJOR VEHICLE EXIT LOCATIONS TO MINIMIZE VEHICLE TRACKING OF SEDIMENT FROM THE PROJECT ONTO PAVED SURFACES. BMPS TO PROTECT VEHICLE EXIT SITES SHALL BE PAID FOR AS TEMPORARY ROCK CONSTRUCTION ENTRANCE. THE CONTRACTOR IS RESPONSIBLE FOR INSURING PAVED STREETS ARE CLEAN AT THE END OF EACH WORKING DAY. TRACKED SEDIMENT ON PAVED STREETS MUST BE REMOVED BY STREET SWEEPING WITHIN 24 HOURS OF DISCOVERY. STREET SWEEPING SHALL BE INCIDENTAL.

TEMPORARY SOIL STOCKPILES, IF REQUIRED, MUST HAVE EFFECTIVE SEDIMENT CONTROLS AROUND THE PERIMETER AND CANNOT BE PLACED IN SURFACE. WATERS, INCLUDING STORM WATER CONVEYANCES SUCH AS CURB OR GUTTER SYSTEMS OR DITCHES. SEDIMENT CONTROLS FOR SOIL STOCKPILES SHALL BE INCIDENTAL.

OTHER MATERIAL STOCKPILES THAT WILL REMAIN ON SITE SHALL BE COVERED BY PLASTIC SHEETING AT THE END OF EVERY WORK DAY.

POLLUTION PREVENTION:

HAZARDOUS MATERIALS SUCH AS OIL AND FUEL MUST BE PROPERLY STORED, INCLUDING SECONDARY CONTAINMENT, TO PREVIENT SPILLS, LEAKS, OR OTHER DISCHARGE FROM ENTERING MILLE LACS LAKE. RESTRICTED ACCESS TO STORAGE AREAS MUST BE PROVIDED TO PREVENT VANDALISM. STORAGE AND DISPOSAL OF HAZARDOUS WASTE MUST BE IN COMPLIANCE WITH MPCA REGULATIONS. THE CONTRACTOR WILL BE REQUIRED TO SUBMIT A SITE PLAN FOR REFUELING METHODS. REFUELING AREAS MUST BE ON LEVEL GRADE AND LOCATED AT LEAST 15 YARDS FROM MILLE LACS LAKE. THE CONTRACTOR SHALL MAINTAIN ADEQUATE SUPPLIES OF ABSORBENT SPILL CLEAN-UP MATERIALS AND SPILL KITS IN FUELING AREAS AND ON MOBILE FUELING EQUIPMENT.

ALL CHEMICAL SPILLS SHALL BE IMMEDIATELY PICKED UP, INCLUDING FERTILIZERS AND PORTABLE URINALS. ALL SPILLED MATERIALS SHALL BE PROPERLY DISPOSED OF OR, IN THE CASE OF FERTILIZER, SPREAD ACCORDING TO MANUFACTURERS RECOMMENDATIONS FOR NPK, OR AS INDICATED IN THE TURF RESTORATION PLAN. THERE SHALL BE NO EQUIPMENT WASHING ON SITE UNLESS IN A PREAPPROVED BY THE PROJECT ENGINEER, AND IN A DESIGNATED SITE WITH TOTAL POLLUTION MANAGEMENT PROGRAM THAT PREVENTS AIR. LAND AND WATER POLLUTION.

ALL MORTAR AND CHEMICAL MIXING SAWING, AND CUTTING OPERATIONS SHALL HAVE SECONDARY CONTAINMENT TO PREVENT CEMENTITIOUS LIQUIDS, SOLIDS AND DUSTS FROM INFILTRATING INTO THE GROUND, LAKE MILLE LACS, OR TRANSPORT BY ANY MEANS TO THE GUTTER, SIDEWALK OR ROAD SURFACE.


ALL CONCRETE OR STONE SAW CUTTING SHALL BE PREVENTED FROM ENTERING STORM WATER CONVEYANCE SYSTEMS AND LAKE MILLE LACS BY USE OF 3897 FILTER LOG, TYPE COMPOST LOG, AND REPLACE AS OFTEN AS NECESSARY TO REMAIN FUNCTIONAL TO FILTER REMOVE FINE CEMENTITIOUS DISCHARGE.

FINAL STABILIZATION:

THE CONTRACTOR MUST ENSURE FINAL STABILIZATION OF ANY DISTURBED AREAS OF THE SITE. FINAL STABILIZATION SHALL INCLUDE A MINIMUM OF 70% VEGETATION ESTABLISHMENT (100% STABILIZED) ON ALL PERVIOUS AREAS DISTURBED.

THE CONTRACTOR MUST ESTABLISH VEGETATIVE COVER OF DISTURBED AREAS BY SODDING OR BY SEEDING AND MULCHING IN ACCORDANCE WITH MN/DOT SPEC. 2575.3. PRIOR TO SODDING OR SEEDING, THE SOIL MUST BE PROPERLY LOOSENED TO A MINIMUM DEPTH Of 6 INCHES.

ALL TEMPORARY EROSION AND SEDIMENT CONTROL BMPS MUST BE REMOVED AS PART OF THE FINAL STABILIZATION, UNLESS DIRECTED OTHERWISE BY THE ENGINEER.



BRANCHES PRUNED AT TRUNK

TOO TOO TOO CORRECT SLANTEĎ LÖNG PRUNING CLOSE CUT LIVE BUD

BRANCHES PRUNED TO LIVE BUD

PRUNING

STEPS TO PRUNING WITH PRUNING

- 1. CUT PART WAY THROUGH THE
- BRANCH AT POINT A. 2. CUT COMPLETELY THROUGH
- BRANCH FROM POINT B TO A. 3. AT BRANCH COLLAR CUT FROM POINT C TO D.

INCORRECT CUT FROM POINT C TO X (TOO CLOSE) WILL RESULT IN DISCONTINUOUS CALLUS FORMATION AFTER ONE SEASON OF GROWTH.

CORRECT CUT FROM POINT C TO D (LEAVING BRANCH COLLAR BUT NOT THE STUB FROM POINT B TO A) WILL RESULT IN CONTINUOUS DOUGHNUT SHAPED CALLUS FORMATION AFTER ONE SEASON OF GROWTH.


PRUNING NOTES:

- 1. PRUNE USING CLEAN AND SHARP SCISSOR-TYPE PRUNER OR PRUNING SAW.
- 2. THE BEST TIME TO PRUNE IS LATE DORMANT SEASON OR
- EARLY SPRING.
 3. AVOID PRUNING OAKS IN APRIL, MAY, JUNE OR JULY.
- 4. IF PRUNING IS NECESSARY OR IF WOUNDS OCCUR TO OAK TREES IN APRIL, MAY, JUNE OR JULY. IMMEDIATELY PAINT CUT SURFACE OR WOUND WITH LATEX PAINT OR SHELLAC.

(Mn/DOT 2571.3K2a9 and 2571.3E1)

FABRICATE 12" X 9" X 3/8" SIGN WITH 0.75" RADIUS CORNERS.

ATTACH SIGN TO POST USING 1"



1. FURNISH AND INSTALL TEMPORARY FENCE AT THE TREE'S DRIPLINE OR CONSTRUCTION LIMITS AS SPECIFIED, PRIOR TO ANY CONSTRUCTION.

2. WHEN POSSIBLE PLACE FENCE 25 FEET BEYOND THE DRIP LINE. 3. PLACE TREE PROTECTION SIGNS ALONG FENCE AT 50' INTERVALS.

DIAMETER AT 4.5 ft ABOVE GROUND MINIMUM DISTANCE FROM TREE TRUNK DIRECTIONAL DRILLING MACHINE BORE TUNNEL MINIMUM TREE PROTECTION ZONE DEPTH OF TUNNEL С <2" 2' 2' 4' 2.5* 2-4" >4-9" 6′ 2.5' 10' > 9-14" 3' >14-19" 12' 3.251 >19" 15' 4"

MEASURE TREE

TEMPORARY FENCE

(MnDOT 2572,3A1)

(MnDOT 2572.3A5)

6" WOODCHIP MULCH

STEEL PLATES


WOODCHIP MULCH BED

TIMBERS


TEMPORARY FENCE REDUCED ROUNDING NORMAL ROUNDING


SIGNIFICANT TREES NEAR THE PROPOSED CONSTRUCTION LIMITS WILL BE IDENTIFIED IN THE PLAN OR BY THE ENGINEER AND WILL BE PRESERVED BY THE CONTRACTOR.

- PLACE THE TEMPORARY FENCE.
 REDUCE SLOPE ROUNDING WHERE ROOT ZONES ARE DISTURBED BY NORMAL SLOPE ROUNDING.
- VARY BACK SLOPE STEEPNESS TO AVOID TREE LOSS OR UNNECESSARY ROOT DAMAGE.



- 1. ANY FILL REQUIRED WITHIN THE DRIP LINE OF TREES, IS UNCOMPACTED SANDY LOAM TOPSOIL IWITH A COARSE SAND COMPONENT).
- EXCESSIVE FILL MAY REQUIRE INSTALLING PERFORATED PIPE WITH AT LEAST ONE DAYLIGHTED END OPENING AS AN AERATION SYSTEM.





- THE TREE ROOTS WILL BE CUT CLEANLY TO THE MAXIMUM DEPTH NECESSARY FOR CONSTRUCTION.
- IMMEDIALTLY, AND CLEANLY CUT DAMAGED AND EXPOSED ROOTS.
- ROOT ENDS EXPOSED BY EXCAVATION ACTIVITIES SHALL BE IMMEDIATELY COVERED WITH A 6" LAYER OF ADJACENT SOIL.

IF CONSTRUCTION VEHICLES MUST PASS OVER ROOT ZONES, THE CONTRACTOR MUST EITHER:

1. CONSTRUCT ROOT SYSTEM BRIDGES WITH STEEL PLATE

SUPPORTED ON WOOD TIMBERS PLACED RADIALLY TO THE TREE TRUNK.

PLACE A 6 INCH LAYER OF WOODCHIP MULCH OVER A TYPE III GEOTEXTILE (Mr/DOT 3733).

OTHER VEGETATION PROTECTION MEASURES

SANDY LOAM TOPSOIL

CLEAN ROOT CUTTING (MnDOT 2572.3A4)

(Mn/DOT 2572.3A2)

DATE PRINTED:

JANUARY /01/2019

SLOPE ROUNDING

OFFICE OF TECHNICAL SUPPORT



STATE OF MINNESOTA OFFICE OF TECHNICAL SUPPORT LANDSCAPE ARCHITECTURE UNIT TRANSPORTATION BUILDING ST. PAUL. MINNESOTA 55155-189

PROTECTION AND RESTORATION OF VEGETATION

UTILITY CONSTRUCTION

SHEET NO.

5 **of** 24


(Mn/DOT 2572.3A12)


STATE PROJECT 1804-87


(TH 169)


ROOT SYSTEM BRIDGE


SHEETS














I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY FILE SERVER LOCATION: LICENSED LANDSCAPE ARCHITECT UNDER THE K:\g-m\MnDOT\14867000\erch\dwgs LAWS OF THE STATE OF MINNESOTA.

PRINTED NAME: KATHRYN J MEFADDEN DATE: SEPTEMBER 12, 2012 LIC. NO. 41742





TRANSPORTATION BUILDING ST. PAUL, MINNESOTA 55155--1899

VISITOR CENTER LAYOUT PLAN

STATE PROJECT 1804-87 (TH169)

SHEET NO. 11 OF 24 SHEETS






1 WALK SECTION


NOTE:

CREATE TRENCHES FOR PIPES AS NEEDED TO ACHIEVE PIPE SLOPES REQUIRED. PLACE 6 IN. COARSE FILTER AGGREGATE AND FOLLOW WITH 6 IN. FINE FILTER AGGREGATE LAYER, AS PER 3/14



2 ALTERNATE PIPE DETAIL

NOT TO SCALE



DATE MODIFIED: 9/12/12

FILE SERVER LOCATION:

K:\g-m\MnDOT\14867000\arch\dwgs

DRAWN BY: DLH CHECKED BY: KJM

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED LANDSCAPE ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA.

SIGNATURE: XATHEYN J. De JudenPRINTED NAMÉ: KATHRYN J. MCPADDEN


DATE: SEPTEMBER 12, 2012 LIC. NO. 41742




STATE OF MINNESOTA DEPARTMENT OF TRANSPORTATION

TRANSPORTATION BUILDING ST. PAUL, MINNESOTA 55155-1899 GARRISON CONCOURSE OVERLOOK — CITY OF GARRISON SUBSURFACE DRAINAGE DETAILS

STATE PROJECT 1804-87 (TH169) SHEET NO. 14 OF 24 SHEETS





KEY NOTES:

- (1) SEE DETAIL 1/22
- (2) SEE DETAIL 2/22
- (3) SEE DETAIL 1/23
- 4 PLACE B624 CURB & GUTTER FROM END OF STONE CURB TO TH169 AS SHOWN.
- (5)6" CONCRETE WALK
- 6 RESTORE HISTORIC SIDEWALK: PLACE SALVAGED AND NEW STONE PAVERS ON AGGREGATE BED. MORTAR JOINTS. SEE DETAIL 2/24.
- 7 RESTORE HISTORIC CURB: PLACE SALVAGED AND NEW STONE CURBING TO MATCH EXISTING. SEE
- 8 PLACE STRIPING FOR 2 HC PARKING SPACES, SEE DETAIL 3/22
- (9) CONTROL JOINT, TYP.
- RELOCATE MISCELLANEOUS STRUCTURE: RELOCATION OF EXISTING VISITORS CENTER BY OTHERS.
- RELOCATE MISCELLANEOUS STRUCTURE: RELOCATE FIBERGLASS WALLEYE TO NEW CONCRETE WALK. ATTACH USING EXISTING STRUCTURE AT WALLEYE BASE WITH NEW ANCHORS INTO NEW CONCRETE WALK.
- CLEAN HISTORIC STRUCTURE: REMOVE DIRT AND CONCRETE RESIDUE FROM STRUCTURE PRIOR TO REPOINTING. PERFORM FINAL CLEANING AFTER STONE INSTALLATION AND REPOINTING.
- PLACE EXPANSION JOINT DESIGN SPECIAL: PLACE EXPANSION JOINT BETWEEN PIER AND WALL, AND BETWEEN PAVERS AND WALL. SEE DETAILS 5/24 AND
- RESTORE HISTORIC WALL: PLACE NEW STONE IN AREAS OF DAMAGED STONE. NEW STONE TO MATCH HISTORIC IN TYPE, SIZE, ORIENTATION, COLOR, TEXTURE,
- REPOINT HISTORIC STRUCTURE: AFTER REMOVAL OF CONCRETE WALK AND REMOVAL/SALVAGING OF HISTORIC PAVERS, REPOINT 100% OF WALL FROM CONCRETE WALK ELEVATION TO 1' FOOT BELOW HISTORIC PLAZA LEVEL. SEE DETAIL 4/24.
- 16) PLACE BENCH: PLACE CONCRETE AND STONE BENCH TO MATCH EXISTING ON SITE. SEE DETAIL 6/24.
- RELOCATE BENCH: RELOCATE EXISTING CONCRETE AND STONE BENCHES ON SITE AND PLACE IN NEW LOCATION. SEE DETAIL 6/24 FOR SIMILAR INSTALLATION DETAILS.
- (18) <u>HANDICAPPED PARKING SIGN</u>: BY OTHERS.

CHECKED BY: RLG

FILE SERVER LOCATION:

K:\g-m\kinDOT\14867000\arch\dwgs

PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED LANDSCAPE ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA.

PRINTED NAME: KATHRYN J MCFADDEN DATE: SEPTEMBER 12, 2012 UC. NO. 41742




TRANSPORTATION BUILDING ST. PAUL, MINNESOTA 55155-1899

GARRISON CONCOURSE OVERLOOK - CITY OF GARRISON CONSTRUCTION PLAN

STATE PROJECT 1804-87 (TH169)

SHEET NO. 16 OF 24 SHEETS



GENERAL NOTES

SEE SPECIAL PROVISIONS FOR SPECIFIC PROJECT REQUIREMENTS.

REFER TO MINDOT SPECIFICATIONS 2571, 3861, AND THE "2010" INSPECTION AND CONTRACT ADMINISTRATION MANUAL FOR MADOT LANDSCAPE PROJECTS" FOR GENERAL REQUIREMENTS.

COMPLETE PREPARATORY WORK BEFORE STARTING INITIAL PLANTING OPERATIONS.

ACCEPT ALL PLANT STOCK IN ACCORDANCE WITH (MINDOT 3861) PRIOR TO PLANTING.

THE CONTRACTOR WILL DEMONSTRATE COMPETENCY FOR SOIL CULTIVATION OPERATIONS IN ACCORDANCE WITH (MINDOT 2571.3D2 STEP 4)

THE CONTRACTOR WILL DEMONSTRATE COMPETENCY FOR ALL PLANT INSTALLATION OPERATIONS IN ACCORDANCE WITH (Mn/DOT 2571.3F1)


CEE CORCIAI DOGGICIONIC AND CTANDADO DI ANTINIC DETAILS (C)

PROTECTION	SEE SPECIAL PROVISIONS AND STANDARD PLANTING DETAILS (C)
FERTILIZER	SEE SPECIAL PROVISIONS
COMPOST	Mn/DOT 3890 GRADE 2 UNLESS OTHERWISE SPECIFIED.
MULCH MATERIAL	Mn/DOT 3882 TYPE 6 UNLESS OTHERWISE SPECIFIED.
Mass Planting Beds	PREPARE MASS PLANTING BEDS FOR PLANTS PLACED AT 15' OR LESS, UNLESS OTHERWISE SPECIFIED ON SHEETS. PLANT BEDS IN STAGGERED ROWS ON THE PERIMETER FIRST, THEN UNIFORMLY FILL IN WITH REMAINING PLANTS, USE TRIANGULAR SPACING, UNLESS SPECIFIED OTHERWISE. PROVIDE 5' RADIUS CLEAR OF SHRUBS AROUND EACH DECIDUOUS TREE AND 8' CLEAR RADIUS AROUND EACH CONIFER TREE. RADIUS WILL BE MEASURED FROM THE CENTER OF THE TREE TO THE CENTER OF THE SHRUB. NOTIFY ENGINEER OF GROSS PLANT QUANTITY SURPLUS OR DEFICIENCY IMMEDIATELY. MULCH ENTIRE MASS PLANTING BED. SEE STANDARD PLANTING DETAILS (C)

TREE PAINTING (FROST CRACK PREVENTION)	PAINT OAK, LINDEN, LOCUST, MAPLE, CRABAPPLE AND MOUNTAIN ASH. ONLY UNDILUTED EXTERIOR WHITE LATEX PAINT IS ACCEPTABLE. PAINT TREE CIRCUMFERENCE FROM GROUND LINE TO FIRST MAJOR BRANCH.				
LANTING PLAN DIMENSIONS	STATED DIMENSIONS SUPERCEDE SCALING FROM PLAN.				
70	PLANT TYPE	AVERAGE GALLONS OF WATER PER APPLICATION			
2571.3G)	MACHINE TRANSPLANTED TREES	50–100			
_	BALLED AND BURLAPPED TREES	20			
(Мг⁄рот	BARE ROOT AND CONTAINER TREES	15			
	BALLED AND BURLAPPED SHRUBS	10			
GUIDELINES	BARE ROOT AND CONTAINER SHRUBS	7			
	WOODY SEEDLINGS	4			
VATERING	PERENNIALS AND VINES	3			
VATE	IT IS THE CONTRACTOR'S RESPONSIBILITY TO MONITOR AND MAINTAIN SOIL MOISTURE AT ADEQUATE BUT NOT EXCESSIVE				

LEVELS. THE AMOUNTS LISTED ABOVE ARE GUIDELINES, NOT

REQUIREMENTS.



PROJECT LOCATION

- BARE ROOT PERENNIALS MUST BE INSTALLED IN THE SPRING NO LATER THAN JUNE 1ST OR FOLLOW THE FALL DECIDUOUS PLANTING DATES.
- ACTUAL DATES MAY CHANGE DEPENDING UPON SEASONAL CONDITIONS, AS DETERMINED BY THE ENGINEER.
- FALL PLANTING IS NOT ALLOWED FOR BARE ROOT FORM OF THE FOLLOWING SPECIES: HAWTHORN, DOGWOOD, POPLAR, HACKBERRY, LINDEN, IRONWOOD, HONEYLOCUST, BIRCH, MOUNTAIN ASH, MAPLE, WILLOW, CRABAPPLE, PLUM/CHERRY, OAKS, AND SUMAC.
- 4. ALL REPLACEMENT PLANTS MUST BE INSTALLED DURING THE MONTH OF MAY DURING THE FIRST YEAR OF THE PLANT ESTABLISHMENT PERIOD.

PLANTING DATES BY ZONE						
KEY	SPRING				FALL	
DECIDUOUS CONIFEROUS PERENNIALS SEEDLINGS DECIDUOUS CON					CONIFEROUS	
	APRIL 21	APRIL 21	MAY 1	APRIL 21	OCT. 1	AUG. 25
	TO	TO	то	TO	TO	то
ШПШ	JUNE 1	JUNE 1	JUNE 15	JUNE 1	NOV. 1	SEPT. 15
	APRIL 7	APRIL 7	MAY 1	APRIL 7	OCT. 10	AUG. 25
(/(2)//	TO	TO	TO	TO	то	то
	JUNE 1	MAY 17	JUNE 15	MAY 17	NOV. 15	SEPT. 15

CANADA

ZONE 2

PLANT INSTALLATION PERIOD


(Mn/DOT 2571.3F2)

-40°TO -50°F

-30"TO -40" F / -20°TO -30°F

(Mn/DOT 3861.2C)

ZONE MAP ZONES LEGEND MIN. TEMP.




BRANCHES PRUNED AT TRUNK

700 TOO

LONG

SLANTED



BRANCHES PRUNED TO LIVE BUD

PRUNING

CORRECT

PRUNING

CUT

T00

CLOSE

STEPS TO PRUNING WITH PRUNING SAW


- 1. CUT PART WAY THROUGH THE
 - BRANCH AT POINT A. 2. CUT COMPLETELY THROUGH
 - BRANCH FROM POINT B TO A. 3. AT BRANCH COLLAR CUT FROM POINT C TO D.

INCORRECT CUT FROM POINT C TO X (TOO CLOSE) WILL RESULT IN DISCONTINUOUS CALLUS FORMATION AFTER ONE SEASON OF GROWTH.


CORRECT CUT FROM POINT C TO D (LEAVING BRANCH COLLAR BUT NOT THE STUB FROM POINT B TO A) WILL RESULT IN CONTINUOUS DOUGHNUT SHAPED CALLUS FORMATION AFTER ONE SEASON OF GROWTH.

PRUNING NOTES:

- 1. PRUNE USING CLEAN AND SHARP SCISSOR-TYPE PRUNER OR PRUNING SAW.
- 2. THE BEST TIME TO PRUNE IS LATE DORMANT SEASON OR EARLY SPRING.
- 3. AVOID PRUNING OAKS IN APRIL MAY, JUNE OR JULY.
- IF PRUNING IS NECESSARY OR IF WOUNDS OCCUR TO OAK TREES IN APRIL, MAY, JUNE OR JULY, IMMEDIATELY PAINT CUT SURFACE OR WOUND WITH LATEX PAINT OR SHELLAC.



PRIMARY TILLAGE - PASS 1



4 INCHES OF GRADE 2 COMPOST AND OTHER SPECIFIED ADDITIVES THOROUGHLY MIXED WITH INPLACE CULTIVATED SOILS

INCORPORATION TILLAGE - PASS 2

PLANTING SOIL

(Mn/DOT 2571.3D2)

ACCEPTABLE PLANT STOCK GROWING RANGE LIMITS

YEARS WITHIN THE ACCEPTABLE LIMITS SHOWN,

IN

FOR ALL PLANT STOCK, DOCUMENT ACCEPTABILITY FOR HARDINESS IN THE

MINNESOTA ZONE WHERE THE PROJECT SITE IS LOCATED, AS FOLLOWS:

SOURCE: USDA PLANT HARDINESS ZONE MAP

ZONE 5

UNACCEPTABLE

MO

CO

KS

DEPARTMENT OF TRANSPORTATION OFFICE OF TECHNICAL SUPPORT LANDSCAPE ARCHITECTURE UNIT TRANSPORTATION BUILDING ST. PAUL, MINNESOTA 55155-1899

STANDARD PLANTING DETAILS (A)

STATE PROJECT 1804-87

SHEETS

DATE PRINTED: JANUARY /01/2011

RODENT


OFFICE OF TECHNICAL SUPPORT

DRAWN BY

B. PLANT STOCK, GROWN OUTSIDE THE ACCEPTABLE GROWING RANGE LIMITS, HAVING SEED SOURCE OR ROOT AND GRAFT STOCK ORIGINATING FROM THE ACCEPTABLE LIMITS SHOWN.

A. PLANT STOCK CONTINUOUSLY GROWN FOR AT LEAST THE LAST TWO

PLANTING HOLE DIMENSIONS HOLE DEPTH FOR BRB AND CONTAINER PLANTS SHALL NOT EXCEED MEASUREMENT FROM ROOT FLAIR TO BOTTOM OF SOIL BALL. PLANT SIZE UP TO (A) MINIMUM HOLE (B) APPROXIMATE PLANT TYPE AND INCLUDING WIDTH 3° B.A 8.75" B.FI 1.25" B.R. 1.5 B.R. 2" B.R. DECIDUOUS & ORNAMENTAL 4 8.8 5' 8.8. A' BB 10' B.B. 1" 8.8 2" B.S. 2.6" B.S. 3.6° B.6. 4" B.B. 12" B.R. 15" B.FL DECIDUOUS 18" B.R. SHRUBS, ROSES AND PERENNIALS 2' B.R. 6 B.R PERENNIAL HOLE DEPTH AND WIDTH SHALL BE BASED UPON ON-CENTER SPACING IN A CONTINUOUS TRENC 2' B.B.




INSTALLATION OF VINES

DATE PRINTED:

JANUARY /01/2018


DRAWN BY

OFFICE OF TECHNICAL SUPPORT



- 1. SCARIFY SIDES AND BOTTOM OF HOLE.
- 2. PROCEED WITH CORRECTIVE PRUNING.
- 3. SET PLANT ON UNDISTURBED NATIVE SOIL OR THOROUGHLY COMPACTED PLANTING SOIL. INSTALL PLANT SO THE ROOT FLARE IS AT OR UP TO 2" ABOVE THE FINISHED GRADE WITH BURLAP AND WIRE BASKET, (IF USED), INTACT.
- 4. SLIT REMAINING TREATED BURLAP AT 6" INTERVALS.
- 5. BACKFILL TO WITHIN APPROXIMATELY 12" OF THE TOP OF THE ROOTBALL, THEN WATER PLANT,
- 6. REMOVE THE TOP 1/3 OF THE BASKET OR THE TOP TWO HORIZONTAL RINGS WHICHEVER IS GREATER. REMOVE ALL BURLAP AND NAILS FROM THE TOP 1/3 OF THE BALL. REMOVE ALL TWINE. REMOVE OR CORRECT STEM GIRDLING
- 7. PLUMB AND BACKFILL WITH PLANTING SOIL.
- WATER THOROUGHLY WITHIN 2 HOURS TO SETTLE PLANTS AND FILL VOIDS.
- 9. BACK FILL VOIDS AND WATER A SECOND TIME.
- 10. PLACE MULCH WITHIN 48 HOURS OF THE SECOND WATERING UNLESS SOIL MOISTURE IS EXCESSIVE.


BALLED & BURLAPPED STOCK



- 1. SOAK ROOTS IN WATER FOR AT LEAST ONE HOUR BUT NOT MORE THAN 24 HOURS PRIOR TO PLANTING.
- 2. SCARIFY SIDES AND BOTTOM OF HOLE.
- 3. PROCEED WITH CORRECTIVE PRUNING OF THE TOP AND
- 4. TRANSFER PLANT DIRECTLY FROM WATER TO HOLE. SET PLANT SO THE ROOT FLARE IS AT THE FINISHED SOIL ELEVATION. SPREAD ROOTS OUT EVENLY, PLUMB AND IMMEDIATELY BACKFILL WITH PLANTING SOIL.
- 5. WATER THOROUGHLY WITHIN 2 HOURS TO SETTLE PLANTS AND FILL VOIDS,
- 6. BACK FILL VOIDS AND WATER A SECOND TIME,
- 7. PLACE MULCH WITHIN 48 HOURS OF THE SECOND WATERING UNLESS SOIL MOISTURE IS EXCESSIVE.


INSTALLATION OF PLANTS

BARE ROOT STOCK



- 1. SCARIFY SIDES AND BOTTOM OF HOLE
- 2. PROCEED WITH CORRECTIVE PRUNING OF TOP AND ROOT. 3. REMOVE CONTAINER AND SCORE OUTSIDE OF SOIL MASS TO REDIRECT AND PREVENT CIRCLING FIBROUS ROOTS. REMOVE OR CORRECT STEM GIRDLING ROOTS.
- 4. SET PLANT ON UNDISTURBED NATIVE SOIL OR THOROUGHLY COMPACTED PLANTING SOIL INSTALL PLANT SO THE TOP OF THE ROOT FLARE IS AT OR UP TO 2" ABOVE THE FINISHED GRADE.
- 5. PLUMB AND BACKFILL WITH PLANTING SOIL
- 6. WATER THOROUGHLY WITHIN 2 HOURS TO SETTLE PLANT AND FILL VOIDS.
- 7. BACK FILL VOIDS AND WATER A SECOND TIME.
- 8. PLACE MULCH WITHIN 48 HOURS OF THE SECOND WATERING UNLESS SOIL MOISTURE IS EXCESSIVE.

CONTAINER STOCK



- 1. SCARIFY SIDES AND BOTTOM OF HOLE.
- 2. PROCEED WITH CORRECTIVE PRUNING.
- 3. SET PLANT ON NATIVE SOIL AT SAME DEPTH AS IT WAS PREVIOUSLY GROWN.
- 4. PLUMB AND BACKFILL WITH PLANTING SOIL
- 5. AFTER PLANTING, LOOSEN THE SOIL IMMEDIATELY ADJACENT TO THE ROOT BALL TO A MINIMUM DISTANCE OF 18" AND A MINIMUM DEPTH OF 12".
- 6. WATER THOROUGHLY WITHIN 2 HOURS TO SETTLE PLANT AND FILL VOIDS.
- 7. BACK FILL VOIDS AND WATER A SECOND TIME.
- 8. PLACE MULCH WITHIN 48 HOURS OF THE SECOND WATERING UNLESS SOIL MOISTURE IS EXCESSIVE.

MINIMUM	TREE SPA	DE SIZE RE	QUIREMENTS
(C) SPADE DIAMETER SIZE	OAK TREE, CALIPER	DECIDUOUS/ ORNAMENTAL TREE,CALIPER	CONIFEROUS TREE, HEIGHT
42"	1" to 1.5"	2" to 3"	5' to 7'
60"	1.5" to 2.5"	3" to 4"	7' to 9'
78*	2.5" to 3.5"	4" to 6"	9' to 14'
85"	3.5" to 5"	6" to 8"	14' to 18'

MACHINE MOVED STOCK

PLANTING HOLE DIMENSIONS HOLE DEPTH FOR BUB AND CONTAINER PLANTS SHALL NOT EXCEED MEASUREMENT FROM ROOT FLAIR TO SOTTOM OF SOIL BALL. PLANT SIZE UP TO (A) MINIMUM HOLE (B) APPROXIMATE PLANT TYPE AND INCLUDING 2 8.6 CONIFEROUS TREES IT LEAST 23 OF ALI CONIFER BRANCHES WILL CONTAIN TERMINAL BUDS 12' B.B CONIFEROUS SHRUBS 3' B.B. CONIFEROUS 18" SPR B.B. CELLPACKS / PLUGS 3.5° CONT 4" CONT. 67 OT CONT. CONTAINER 2# CONT 5# CON 15# COA 10# CONT. 25# CONT. 9" SEEDLING SEEDLINGS 15" SEEDLING 2' SEEDUNG 1 YR. MED B.R. 1 YR. NO. 1 B.R. VINES 2 YR. MED. B.R. 2 YR. NO. 1 B.R.

	MULCH AREA CALCULATOR		
	TYPE OF PLANT	SQ. FT. PER PLANT	
	CONIFEROUS TREES	$\left[\left(\frac{3.75 \times HEIGHT}{2}\right) + 3\right]^{2} \times \uparrow \uparrow \uparrow$	
	DECIDUOUS AND ORNAMENTAL TREES	3²× 1 Y	
W.	CONIFEROUS AND DECIDUOUS SHRUBS, ROSE BUSHS, PERENNIALS, ORNAMENTAL GRASS	SPACING × SPACING	
	VINES	SPACING x 2	
	MACHINE-MOVED TREES OR SHRUBS	$\left[\left(\frac{\text{SPADE DIAMETER}}{2}\right) + 1\right]^2 \times \uparrow \uparrow \uparrow$	
		7 7 = 3.1416	
SPACING CONIFEROUS TREE DECIDIOUS TRANSPLANT IF	FROM TRUNK E (RADIUS+3") TREE (3") IADIUS+2")	PULL MULCH BACK NO LESS THAN 3" AND NO MORE THAN 6" FROM TREE TRUNKS. SUBSIDING OR DETERIORATING MULCH IS ACCEPTABLE THROUGHOUT THE ESTABLISHED PERIOD IF THE MULCH DEPTH IS MAINTAINED AT A MINIMUM 3" DEPTH. ADD MULCH WHEN BELOW THE 3" MINIMUM DEPTH, DO NOT EXCEED THE 6" MAXIMUM DEPTH. MULCH CONTAMINATED WITH SOIL MUST BE	
		REMOVED AND REPLACED.	

MULCH PLACEMENT (Mn/DOT 2571.3F)


(Min/DOT 2571.3H)

DEPARTMENT OF TRANSPORTATION LANDSCAPE ARCHITECTURE UNIT ST. PAUL MINNESOTA 55155-1893

STANDARD PLANTING DETAILS (B)

STATE PROJECT 1804-87 (T.H. 169)

SHEET NO. 19 OF 24 SHEETS



- 1. EXCAVATE HOLE OR BED TO ALLOW PLACING THE TOP OF ROOT MASS 1"-3" HIGHER THAN
- 2. AUGER 8" DIAMETER HOLES ENTIRELY THROUGH IMPERVIOUS OR POORLY DRAINED HARD PAN SOIL
- LAYER TO ADEQUATELY DRAIN SUBSOIL.

 3. TEST FOR POSITIVE DRAINAGE. RE-AUGER AN ADDITIONAL 8" IF NECESSARY FOR POSITIVE

5. COMPLETE PLANTING ACCORDING TO ROOT TYPE. SEE STANDARD PLANTING DETAILS (B).


- 4. THOUROUGHLY BACKFILL AUGER HOLES WITH A UNIFORM INCORPORATED MIXTURE OF 50% SAND

INSTALL GRANULAR FILTER

FOR PLANTING SOIL DETAIL SEE STANDARD MULCH PLANTING DETAILS (A) 4" DRAIN TILE

- 1. EXCAVATE HOLE OR BED TO ALLOW PLACING THE TOP OF THE ROOT MASS 1"-3"
- 2. INSTALL 4" MINIMUM DIAMETER DRAIN TILE DAYLIGHTING AT A LOWER GRADE,
- 3. COMPLETE PLANTING ACCORDING TO ROOT TYPE. SEE STANDARD PLANTING DETAILS (B).

INSTALL TILE DRAINAGE




- 1. EXCAVATE HOLE OR BED 14 THE DEPTH OF THE ROOT MASS. 2. SET ROOT MASS IN HOLE.
- 3. CONSTRUCT BERM WITH PLANTING SOIL EXTEND THE BERM BASE TO A WIDTH OF 3
- 4. COMPLETE PLANTING ACCORDING ROOT TYPE. SEE STANDARD PLANTING DETAILS (B).

INSTALL MINI-BERM


1. THE NEED FOR USING PLANTING DETAILS FOR POORLY DRAINED SOILS AND WHICH TYPE TO USE ARE DETERMINED BY THE CONTRACTOR, SUBJECT TO ENGINEER APPROVAL.

PLANTING DETAIL FOR POORLY DRAINED SOILS

(Mn/DOT 2571.3D2 (STEP 8



PLANTING ON SLOPES



- 1. FORM A DOUBLE-LAYERED CYLINDER USING 0.25" GRID GALVANIZED WELDED WIRE MESH (HARDWARE CLOTH). OVERLAP THE CUT END 2".

 2. DRIVE TWO 1" x 1" OPPOSING HEARTWOOD WHITE OAK STAKES INTO THE GROUND, 7" FROM THE
- CENTER OF THE TREE STEM.

 3. SECURE THE MESH CYLINDER TO THE OUTSIDE OF THE STAKES USING EITHER, SCREWS AND WASHERS
- OR CABLE-TIES ALONG THE OVERLAP. SPACE APPROXIMATELY 4" ON CENTER ALONG THE OVERLAP.

 a. SCREWS SHALL BE ROUND HEAD GALVANIZED 18" DIA. x 34" LONG WITH WASHERS.
- b. CABLE-TIES SHALL BE NYLON, AT LEAST 8" LONG AND BETWEEN 75LB TO 120LB TENSILE
- 4. EMBED THE LOWER EDGE OF THE MESH CYLINDER 1" BELOW THE SOIL SURFACE WITHOUT DISTURBING
- THE TREE ROOTS.
 5. CUT EDGES WILL NOT BE PERMITTED AT THE TOP OF THE CYLINDER. STAKE WILL BE FLUSH WITH THE TOP OF THE CYLINDER.
- 6. MULCH WITHIN THE CYLINDER SHALL NOT EXCEED 3" DEPTH AND SHALL BE PULLED BACK FROM THE TRUNK AS SPECIFIED IN MULCH PLACEMENT DETAIL.
- 7. THE BOTTOM WHORL OF PINE AND LARCH BRANCHES MAY HAVE TO BE REMOVED TO PERMIT INSTALLATION OF 12" MIN. HEIGHT RODENT GUARDS.
 8. INSTALL ON ALL DECIDUOUS, PINE AND LARCH TREES, DO NOT PLACE ON SPRUCE TREES.

RODENT PROTECTION

USE SEAMLESS, EXTRUDED, TWIN-WALL, RIGID AND SEMI

PERFORATION AND AN OUTWARD-FLARED TOP RIM.

TWISTING.

TRANSLUCENT POLYPROPYLENE TUBES WITH A LASER LINE

SECURE SHELTER WITH NYLON


x 1" WHITE OAK STAKE TO PREVENT DISLODGING OR

EMBED THE BOTTOM OF THE

NETTING DOWN AS SHOWN.

INSTALL A PLASTIC

(Mn/DOT 2571,312)




SEEDLING TREE SHELTER

(Mn/DOT 2571,314)

HOLE EXCAVATION WIDTH IN ACCORDANCE WITH MINIMUMS FROM THE PLANTING HOLE DIMENSIONS CHART ON STANDARD PLANTING DETAILS (B) FOR PLANTING SOIL **DETAIL SEE STANDARD -**PLANTING DETAILS (A) 5' FOR DECIDUOUS TREES MULCH-8' FOR CONIFEROUS TREES

PLANT SPACING IN MASS BEDS



16" LONG POLYROPYLENE OR POLYETHYLENE, 40 MIL. THICK AND 1.5" WIDE STRAPS, ATTACH WITH 10 ga WIRE.

- 1. STEEL POSTS TO BE NOTCHED OR DRILLED TO RETAIN GUY WIRES. PLACE OUTSIDE OF ROOT BALL DRIVE PLUMB REGARDLESS OF GROUND SLOPE.
- 2. REQUESTS TO SUBSTITUTE RUBBER HOSE AND WIRE **GUYING SYSTEMS WILL NOT** BE APPROVED.
- 3. TREE STAKING IS NOT REQUIRED UNLESS SPECIFIED OR NECESSARY TO MAINTAIN TREES IN A PLUMB CONDITION WHERE VANDALISM, SOIL, OR WIND CONDITIONS ARE A PROBLEM, OR AS DIRECTED BY THE ENGINEER.
- 4. REMOVE WITHIN ONE YEAR.

STEEL POST SIZING CALIPER STEEL POST TYPE С В ROLLED STEEL FENCE 3'-0" MIN. POST (Mn/DOT 3403) OR APPROVED EQUA 7'-0 4'-0" 3'-0" 4 INCHES 10', 2.2 LB, FLANGED CREATER CHANNEL STEEL SIGN 4'-0" MIN. THEN 4 6'-0" 5'-0" POST (Mn/DOT 3401)

STAKING AND GUYING

(Mn/DOT 2571.311)

DEPARTMENT OF TRANSPORTATION OFFICE OF TECHNICAL SUPPORT LANDSCAPE ARCHITECTURE UNIT ST. PAUL. MINNESOTA 55155-1899

STANDARD PLANTING DETAILS (C)

STATE PROJECT 1804-87

SHEET NO. 20 OF 24


SHEETS

DATE PRINTED: JANUARY /01/2011

OFFICE OF TECHNICAL SUPPORT

DRAWN BY


(T.H. 169)





NOTE: AGGREGATE WALK TO BE STABLIZED WITH PORTLAND CEMENT USING THE FOLLOWING PROCESS:


- 1. ENSURE MATERIALS ARE KEPT DRY BEFORE AND DURING EARLY STAGES OF INSTALLATION. 2. IN AREAS WHERE WALK WILL CROSS PIPE, PLACE AGGREGATE BASE AS PER DETAIL 1/14 AT APPROPRIATE DEPTH TO ACCOMMODATE 6 INCH DEPTH WALK AT GRADES SPECIFIED (SEE
- PLACE EDGER SO TOP EDGE WILL BE FLUSH WITH FINISH GRADE OF AGGREGATE WALK.
 ON SITE, IMMEDIATELY BEFORE WALK INSTALLATION, THOROUGHLY MIX INTO AGGREGATE 3% PORTLAND CEMENT, KEEPING MATERIALS FREE OF DEBRIS OR OTHER MATERIALS.
 PLACE AND COMPACT AGGREGATE—CEMENT MIX 6—IN DEPTH.
 MOSTEN, WALK THOROUGHLY BUT NOT TO CATURATION BY SERVINGIAND WATER.
- MOISTEN WALK THOROUGHLY, BUT NOT TO SATURATION, BY SPRINKLING WATER.
- COVER WALKS WITH PLASTIC, SECURE EDGES WITHOUT MARRING AGGREGATE, AND LEAVE UNDISTURBED FOR 72 HOURS.











STEEL EDGING DETAIL FOR PLANTING AREAS NTS



STATE OF MINNESOTA DEPARTMENT OF TRANSPORTATION

GARRISON CONCOURSE OVERLOOK - CITY OF GARRISON SITE DETAILS


TRANSPORTATION BUILDING ST. PAUL, MINNESOTA 55155-1899


STATE PROJECT 1804-87 (TH169)

SHEET NO. 21 OF 24 SHEETS

FILE SERVER LOCATION:

LAWS OF THE STATE OF MINNESOTA.







SIGNATURE Xather a De Judden

DATE: SEPTEMBER 12, 2012 LIC. NO. 41742

PRINTED NAME: KATHRYN J WEFADDEN







STATE OF MINNESOTA DEPARTMENT OF TRANSPORTATION

TRANSPORTATION BUILDING ST. PAUL, MINNESOTA 55155-1899


GARRISON CONCOURSE OVERLOOK - CITY OF GARRISON SITE DETAILS

STATE PROJECT 1804-87 (TH169)

SHEET NO. 22 OF 24 SHEETS

DATE MODIFIED:

12 SEPT 2012



1 PEDESTRIAN CURB RAMP — 6" CONCRETE WALK
0 2 4 SCALE IN FEET

STONE CURB

STONE CURB


FOR WALK
ENTRANCE

STONE CURB AT DRIVE

CONC. RETURNED CURBS
BEHIND STONE CURB, ALONG
CONCRETE WALK

CONC. RETURNED CURBS
BEHIND STONE CURBS
BEHIND STONE CURBS
BEHIND STONE CURB, ALONG
CONCRETE WALK

ELEVATION A—A



SECTION B-B

DATE MODIFIED: 12 SEPT 2012

FILE SERVER LOCATION:

K:\g-m\MnDOT\14867000\arch\dwgs

DRAWN BY: JJZ CHECKED BY: RLG

I HEREBY CERTIFY THAT THIS PLAN WAS

PREPARED BY ME OR UNDER MY DIRECT

SUPERVISION AND THAT! AM A DULY

LICENSED LANDSCAPE ARCHITECT UNDER THE

LAWS OF THE STATE OF MINNESOTA.




STATE OF MINNESOTA DEPARTMENT OF TRANSPORTATION


TRANSPORTATION BUILDING ST. PAUL, MINNESOTA 55155-1899 GARRISON CONCOURSE OVERLOOK — CITY OF GARRISON SITE DETAILS

STATE PROJECT 1804-87 (TH169)


SHEET NO. 23 OF 24 SHEETS




•




CONCRETE WALK EDGES ADJACENT TO CONCRETE STRUCTURES




RAILROAD CROSSING PLAN VIEW




V CURB ADJACENT TO LANDSCAPE CURB WITHIN SIDEWALK LIMITS



V CURB ADJACENT TO LANDSCAPE CURB OUTSIDE SIDEWALK LIMITS



DETECTABLE EDGE AT QUADRANT (5)



V CURB INTERSECTION

TE CURB GN V						
CURB WIDTH W			_			
4"						
6"			_	T	_	
6) 4 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	EXISTING WALK		EXISTING BUILDING			A VARIABLE S
				0 4	Ü A	2
	V	CURB	ADJACENT	ΤO	BUILDING	

NOTES:

CONCRET

HEIGHT

< 6"

≥6"

DESIG CURB

ALL V-CURB CONTRACTION JOINTS SHALL MATCH CONCRETE WALK JOINTS.

- V CURB SHALL BE PLACED OUTSIDE THE SIDEWALK LIMITS WHEN RIGHT OF WAY ALLOWS.

 V CURB NEXT TO BUILDING SHALL BE A 4" WIDTH AND SHALL MATCH PREVIOUS TOP OF SIDEWALK ELEVATIONS.
- (1) END TAPERS AT TRANSITION SECTION SHALL MATCH INPLACE SIDEWALK GRADES.
- (2) ALL V CURB SHALL MATCH BOTTOM OF ADJACENT WALK.
- 3 EDGE BETWEEN NEW V CURB AND INPLACE STRUCTURE SHALL BE SEALED AND BOND BREAKER SHALL BE USED BETWEEN EXISTING STRUCTURE AND PLACED V-CURB.
- 4 EDGE OF DETECTABLE WARNING SURFACES SHALL BE PLACED 6'MINIMUM TO 15' MAXIMUM FROM THE CENTERLINE OF THE NEAREST RAIL. WHEN PEDESTRIAN GATES ARE PROVIDED, DETECTABLE WARNING SURFACES SHALL BE PLACED ON THE SIDE OF THE GATES OPPOSITE THE RAIL.
- (5) ALL CONSTRUCTED CURBS MUST HAVE A CONTINUOUS DETECTABLE EDGE FOR THE VISUALLY IMPAIRED. THIS DETECTABLE EDGE REQUIRES TRUNCATED DOMES WHEREVER THERE IS ZERO-INCH HIGH CURB. CURB TRANSITIONS ARE CONSIDERED A DETECTABLE EDGE WHEN THE TAPER STARTS IMMEDIATELY AT THE EDGE OF THE TRUNCATED DOMES AND UNIFORMLY RISES TO A 3-INCH MINIMUM CURB HEIGHT. ANY CURB NOT PART OF A CURB TRANSITION AND LESS THAN 3 INCHES IN HEIGHT IS NOT CONSIDERED A DETECTABLE EDGE AND THEREFORE IS NOT COMPLIANT WITH ACCESSIBILTY GUIDELINES.

STANDARD PLAN SHEET NO.
5-297.250 (5 OF 5)

STANDARD APPROVED:
MAY 10, 2012

PEDESTRIAN CURB RAMP DETAILS

STATE PROJ. NO. 1804-87 (TH 169) SHEET NO. 24A OF 24 SHEETS