

TIED TO OUTFALL

DRY SWALE CROSS-SECTION (WITH CHECKDAM)

NOT TO SCALE

FILTER FABRIC

PERFORM CONTINUOUS INSPECTIONS OF EROSION CONTROL PRACTICES.

- 2. INSTALL SILT FENCE ALONG THE PERIMETER OF THE SITE TO PREVENT SEDIMENT FROM LEAVING THE SITE DURING THE CONSTRUCTION PROCESS.
- ALL DOWNGRADIENT PERIMETER SEDIMENT-CONTROL BMPS MUST BE IN PLACE BEFORE ANY UP GRADIENT LAND-DISTURBING ACTIVITY BEGINS.
- REMOVE TOPSOIL FROM THE SITE AND PLACE IN TEMPORARY STOCKPILE LOCATION.
- INSTALL UNDERGROUND UTILITIES (WATER, SANITARY SEWER, ELECTRIC AND PHONES) TAKING THE LOCATION AND FUNCTION OF STORM WATER BMPS INTO CONSIDERATION.
- 7. SEED AND MULCH DISTURBED AREAS ON SITE.
- CONSTRUCT THE ROADS TAKING THE LOCATION AND FUNCTION OF STORM WATER BMPS
- PERFORM ALL OTHER SITE IMPROVEMENTS TAKING THE LOCATION AND FUNCTION OF THE STORM WATER BMPS INTO CONSIDERATION.
- 11. STABILIZE THE SITE BY IMPLEMENTING THE NATIVE SEEDING AND PLANTING PORTION OF
- 12. INSTALL THE EROSION CONTROL BLANKET AND COIR ROLL/CHECK DAMS.
- 13. REMOVE THE SILT FENCE AFTER THE SITE IS STABILIZED PER PROJECT ENGINEER
- INSTALL ALL TEMPORARY EROSION CONTROL MEASURES (IN ACCORDANCE WITH MnDOT GENERAL CONDITIONS 2573) PRIOR TO THE START OF ANY CONSTRUCTION OPERATION THAT MAY CAUSE ANY SEDIMENTATION OR SILTATION AT THE SITE.
- INSTALL STORM DRAIN INLET PROTECTION TO PREVENT CLOGGING OF THE STORM SEWER AND SEDIMENT LOADS TO DOWNSTREAM STORM WATER FACILITIES OR
- GRADING OF THE SWALE SHALL BE ACCOMPLISHED USING LOW-IMPACT EARTH-MOVING EQUIPMENT TO PREVENT COMPACTION OF THE UNDERLYING SOILS. SMALL TRACKED DOZERS AND BOBCATS WITH RUNNER TRACKS ARE RECOMMENDED.
- 5. EXCAVATE THE SWALE TO THE SPECIFIED DEPTH (ELEVATION). IT IS RECOMMENDED THAT ALL SUB MATERIAL BELOW THE SPECIFIED ELEVATION SHALL BE LEFT UNDISTURBED, UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
- GRADE TO THE DEPTH (ELEVATION) SPECIFIED IN THE CONSTRUCTION DOCUMENTS UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
- IN THE EVENT THAT SEDIMENT IS INTRODUCED INTO THE BMP DURING OR IMMEDIATELY FOLLOWING EXCAVATION, THIS MATERIAL WILL NEED TO BE REMOVED FROM THE SWALE PRIOR TO INITIATING THE NEXT STEP IN THE CONSTRUCTION PROCESS. THIS IS ESPECIALLY IMPORTANT IF THE SWALE HAS BEEN DESIGNED TO INFILTRATE STORM. WATER: SEDIMENT THAT HAS BEEN WASHED INTO THE SWALE DURING THE EXCAVATION PROCESS CAN SEAL THE PERMEABLE MATERIAL, SIGNIFICANTLY REDUCING THE INFILTRATION CAPACITY OF THE SOILS.
- MATERIAL EXCAVATED FROM THE SWALE(S) SHALL BE DISPOSED OF ON-SITE AT LOCATIONS (STOCKPILE AREAS) DESIGNATED BY ENGINEER
- NON-STANDARD COMPONENT: CLEAN, WASHED 1.5 TO 3.5-INCH GRAVEL SHALL BE PLACED IN THE BOTTOM OF THE SWALE TO THE DEPTH SPECIFIED IN THE CONSTRUCTION DOCUMENTS. GRAVEL SHOULD BE PLACED IN LIFTS AND LIGHTLY COMPACTED WITH PLATE COMPACTORS.
- NON-STANDARD COMPONENT: THE PERFORATED PIPE (UNDERDRAIN) SHALL BE LAID DIRECTLY ON THE GRAVEL BED. GRADE AND ALIGNMENT SHALL NOT VARY FROM THE PRESCRIBED GRADE BY MORE THAN 0.03 FEET (9 MM) AT ANY POINT. THE JOINTS BETWEEN SECTIONS OF PIPE SHALL BE CONNECTED IN A FASHION ACCEPTABLE TO ENGINEER. ONCE THE PIPE IS IN PLACE, IT SHALL BE COVERED IMMEDIATELY WITH GRANULAR MATERIAL AS SPECIFIED IN THE CONSTRUCTION DOCUMENTS. THE GRANULAR MATERIAL SHALL BE OF UNIFORM DEPTH ON BOTH SIDES OF THE PIPE SPECIAL INLETS AND SPECIAL DEVICES AT THE OUTLET END OF THE PIPE SHALL BE CONSTRUCTED AS SHOWN IN THE PLANS.
- 12. PORTIONS OF SWALE TO BE PLANTED SHALL RECEIVE 3" OF WOODCHIP MULCH (MnDOT
- PORTIONS OF SWALE TO BE SEEDED SHALL BE MULCHED WITH CLEAN GRAIN STRAW (MnDOT TYPE 3) AT A RATE OF 2 TONS PER ACRE.
- 14. SEEDING AND INSTALLATION OF EROSION CONTROL BLANKET SHALL BE COMPLETED WITHIN 48 HOURS OF FINAL GRADING

plan super ofessi State Sign



2005 MINNESOTA STORMWATER MANUAL

WET AND DRY SWALES

Sheet No.